INTERCONNECTION POST-APPROVAL PROCESS

```
┌─────────────────────┐                              ┌─────────────────────┐
│ Utility Approves     │                              │ PM Requests and     │
│ Tier 2 or Tier 4     │───────────┐                  │ Receives Pre-       │
│ Application          │           │                  │ Certification       │
└─────────────────────┘           │                  └─────────────────────┘
          │                        │                             │
          ▼                        │                             ▼
```

⏱ Within 10 days of confirmation of approval.

```
┌─────────────────────┐           │        ╔═══════════════════════════════╗
│ Utility Provides     │           │        ║ Steps Required Between         ║
│ Standard             │           │        ║ Pre-Certification and          ║
│ Interconnection      │           │        ║ Certification                  ║
│ Agreement Form to PM │           │        ║                                ║
└─────────────────────┘           │        ║  ┌─────────────────────┐       ║
          │                        ▼        ║  │ Utility and PM sign  │       ║
          ▼           ┌─────────────────────┐  │ Power Purchase      │       ║
                      │ Utility Initiates    │◄─┤ Agreement           │       ║
                      │ Transmission Service │  └─────────────────────┘       ║
                      │ Request (TSR)        │                                ║
                      └─────────────────────┘                                ║
```

⏱ Within 15 days of receipt of Interconnection Agreement. The PM may also notify the Utility that they wish to negotiate a non-standard agreement in this time period.

```
┌─────────────────────┐   ★ See TSR & deliverability
│ PM Returns Signed    │     upgrades discussion below.
│ Interconnection      │                                 ║  ┌─────────────────────┐  ║
│ Agreement to Utility │─────────────────────────────────╫─►│ PM Constructs       │  ║
└─────────────────────┘                                 ║  │ Project             │  ║
          │                                              ║  └─────────────────────┘  ║
          ▼                                              ║                           ║
```

$ The PM is responsible for reimbursing the utility for the costs of constructing interconnection upgrades. The Utility and PM will agree to a payment schedule for these, and the utility may require a deposit of up to $10,000.

```
┌─────────────────────┐                                 ║  ┌─────────────────────┐  ║
│ Utility Constructs   │                                 ║  │ PM Meets Participant │  ║
│ Interconnection      │                                 ║  │ Enrollment Threshold │  ║
│ Upgrades             │                                 ║  │ for Certification    │  ║
└─────────────────────┘                                 ║  └─────────────────────┘  ║
          │                                              ╚═══════════════════════════╝
          ▼                                                          │
```

⏱ Notice must be provided at least 20 days in advance of commissioning date.

```
┌─────────────────────┐                                              ▼
│ PM Notifies Utility  │                              ┌─────────────────────┐
│ of Intent to Begin   │                              │ PM Requests and     │
│ Operations           │                              │ Receives            │
└─────────────────────┘                              │ Certification       │
          │                                           └─────────────────────┘
          ▼                                                       │
```

⏱ The witness test (and on-site utility inspection) must be scheduled within 10 business days of expected commissioning date. The utility may waive this requirement. Any deficiencies must be noted by the utility within 5 business days, and corrected by the PM within 20 business days.

```
┌─────────────────────┐
│ Utility Conducts     │
│ Witness Test         │
└─────────────────────┘
          │
          ▼
┌─────────────────────┐
│ PM and Utility       │
│ Execute Certificate  │
│ of Completion        │
└─────────────────────┘
          │                                                       │
          ▼◄──────────────────────────────────────────────────────┘
```

⏱ PM must provide written notice to utility 10 days prior to beginning operations.

```
┌─────────────────────┐
│ Project Begins       │
│ Commercial           │
│ Operations           │
└─────────────────────┘
```